# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42426

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020**

**Name of Work:Improvements and Maintenance of Parks in HMT Layout 5th Block in ward no 09 (Vidyaranyapura)**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of MADHUSUDHAN ( ) | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 49.5 | Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods | Cum | 200.0 | Rupees Two Hundred Only |
| 2 | 24.39 | Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work | Cum | 5000.0 | Rupees Five Thousand Only |
| 3 | 48.92 | Plain /Reinforcement Cement Concrete M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, in Open Foundation complete as per Drawing and Technical Specifications Case - I : Using Concrete Mixer" etc complete as per specifications and directions of engineer in charge of the work | Cum | 6000.0 | Rupees Six Thousand Only |
| 4 | 249.3 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work | Cum | 300.0 | Rupees Three Hundred Only |
| 5 | 86 | Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting ( excluding cost of earthwork and concrete) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 910.54 | Rupees Nine Hundred Ten and Fifty Four Paise Only |
| 6 | 170 | Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of | Cum | 400.0 | Rupees Four Hundred Only |
| 7 | 234 | Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work | M | 650.0 | Rupees Six Hundred Fifty Only |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92